

The Development of the Sheffield Highway Maintenance PFI Project

IHT Yorkshire & Humberside Branch Conference 28th January 2010

Ian Kirby Sheffield City Council PFI Project Team Technical Workstream Leader





Introduction

- Background
- Process to Date
- More detail of some of the Process to Date issues eg scope, funding, data, documentation etc
- Lessons learned
- Questions





Background 1 – Scale of the Project and Current Condition

- 2000 km Carriageway and 3400 km Footway bottom quartile for Met Authorities for all 4 BVPI condition indicators
- 65,000 Street Lighting Columns 85% substandard
- 600 Bridges current BCI lower than desirable
- 480 Traffic Signal Sites and a further 300 items of ITS Infrastructure - 30% of stock > 15 years old
- 35,000 Highway Trees 75% mature/over mature



Background 2 – What Is Different About a PFI Contract?

- Government Funding
- Long, fixed term of contract eg 25 years
- Complicated procurement Competitive Dialogue
- Output Specification
 - Majority of risk passed to PFI Provider





Process to Date (1)

- January 2006 Authorities were invited to submit an EOI for a Highway Maintenance PFI project
- February 2006 submitted Expression of Interest for Street Lighting PFI Project
- September 2006 Sheffield submitted Highway Maintenance EOI
- February 2007 Sheffield submitted Street Lighting OBC
- October 2007 Street Lighting OBC approved






Process to Date (2)

- In December 2008 DfT invited 5 of the Authorities that had submitted EOIs, including Sheffield, to refresh their bids and present their proposals
- At the presentation in February 2008, Sheffield were able to demonstrate what they had achieved over the previous 18 months namely:
 - Determination of scope
 - Project Delivery Team established and external advisors appointed
 - Further condition data and inventory collection
 - Further soft market testing
 - Identification of interfaces with Supertram and with other Council projects
 - Additional stakeholder consultation
 - Planning for business transfer of assets, contracts and staff
 - Development of "New Approach" to improve affordability and value for money
 - Broad Political support and approval for additional funding sheffield





Project Delivery Team





Condition and Inventory Data (1)

Carriageway

- 100% CVI
- 100% SCANNER (A,B and C Roads)
- 100% Deflectograph
- Significant levels of SCRIM and Patching Data

Footways

100% DVI (Cat 1, 1a and 2)








Condition and Inventory Data (2)

- Bridges
 - 100% General Inspections (but old)
 - Principal Inspections for 90 key structures
- Street lighting/Signals 100% inventory
- Video survey of entire network







Development of New Approach (1)

- Sheffield's EOI bid (£733m) required all of the national pot of PFI credits
- Since the EOI, inflation and changes in discount rate would have increased this figure so a way of trimming back was required
- Carriageway element of EOI bid had been based on the Network Condition Indicator Approach used on previous Projects
- Original NCI approach heavily dependent on structural condition as measured by Deflectograph which would result in large quantities of full reconstruction which may not actually be necessary and impractical from a traffic management point of view





Development of New Approach (2)

- Went back to basics which led to the "New Approach" and resulted in the development of a new NCI for carriageways (CCI) which included parameters important to stakeholders but excluded the structural requirement
- Enables Service Provider to select less invasive and therefore less disruptive treatments
- Achieves same level of improved safety, ride quality and visual appearance as Eol but at lower cost
- Separate requirement to ensure structural condition does not deteriorate





Process to Date (3)


- March 2008 Chosen as one of three Pathfinder Authorities
- September 2008 PIN issued
- September 2008 Held Industry Day
- September 2008 Gateway Review 1 completed
- September 2008 Soft Market Testing Round 3
- Project (including objectives and scope) approved by Cabinet (September 2008) and by Council (October 2008)
- November 2008 Submitted the Outline Business Case (OBC)
- February 2009 Assessment of OBC by PUK
- March 2009 OBC approved by DfT and PRG (including approval for the full amount of PFI Credits requested -£674.1 m)





Project Funding

- PFI Credits of £674.1 million (including street lighting and rolled up LTP Maintenance funding)
- Council's Highways budgets plus additional £10 million a year
- Total spend of over £2 billion over 25 years







Key Project Objectives

- Step change in the condition of the City's highway
- More accessible and welcoming Streetscene
- Improved safety
- Increased use of public transport
- Reduced crime and fear of crime
- Reduced vehicle maintenance and fuel costs
- Reduced level of 3rd party claims





Project Scope (1)

- Integrated, city-wide, fence-to-fence, whole network approach
- Rehabilitation of the highway network within the first 7 years of the contract
- Maintenance of the highway network for the remaining 18 years of the contract





Project Scope (2)

- Covers all highway assets including:
 - Carriageways, Footways, Structures, Streetlights etc
- Covers soft services including:
 - Street Cleaning, Horticulture/arboriculture, Winter Maintenance etc





Not Included in the Scope

- Retained functions will include most statutory and regulatory duties, especially under the Traffic Management Act
- Grounds maintenance and cleaning of nonhighway land







Process to Date (4)

- April 2009 Gateway Review 2 completed
- April 2009 OJEU issued
- April 2009 Bidders Conference Held
- Development of Project Documentation
 - Project Agreement
 - Output Specification
 - Payment Mechanism





Project Agreement

- Based upon
 - Work undertaken by SCC for Street Lighting Project (based upon Model Street Lighting Contract)
 - Position reached by SCC on other PFI/PPP deals
- Consistent, wherever possible, with SoPC4
- Covers
 - Pre-commencement period
 - Programmes and Method Statements
 - Supervening events
 - Change
 - Warranties and Indemnities
 - Employment matters
 - Handback
 - Dispute resolution
 - Termination





Output Specification

- Started with the Highways Procurement Pack (HPP) Output Specification
- Sets out Performance Requirements
- For each Performance Requirement the following information is also given:
 - Rectification Period
 - Repeat Period
 - Grace Period
 - Adjustment Type
- SCC Output Specification divided into 10 Sections covering specific assets or services





Payment Mechanism

- Annual Unitary Charge starts at 65% and increases to 100% as Milestones are achieved
- Monthly Payment comprises:
 - Monthly Unitary Charge
 - Energy payment
 - Accruals Adjustment
 - Performance Adjustments
 - Carbon Adjustment
 - Traffic Management Adjustment
 - Non Core Services





Milestones

- Carriageway Condition Index (for each hierarchy and Community Assembly Area)
- Footway Condition Index (for each hierarchy and Community Assembly Area)
- Bridge Stock Condition Index (Both Average and Critical for Bridges, Subways and Retaining Walls)
- Replacement of Non Compliant Street Lighting Units
- Replacement of Traffic Signal Installations > 25 years old





Carriageway Condition Index (1)

- Condition data obtained through UKPMS accredited machine and visual Surveys (SCANNER, CVI and SCRIM) together with a bespoke patching survey
- Data processed using UKPMS with modified rule sets and parameters to produce defect ratings
- Defect ratings are then combined and weighted using a bespoke piece of software called Scheme Engineer
- Scheme Engineer produces Sub Section and Section Condition Indices and ultimately CCIs for each hierarchy and Community Assembly Area.





CCI (2) – Relationship Between Defects and Indexes

	Carriageway Condition Index CCI by Network Hierarchy and Community Assembly An Primary and Secondary Road Networks)							
	Section Condition Index	Carriageway Structural CI			Carriageway Surface CI		Carriageway Aesthetic CI	
	Sub Section Condition Index	Struc SSCI	Edge SSCI	Ride SSCI	Surf SSCI	Scrim SSCI	Ride SSCI	Patch SSCI
	Contributing Defects	Wheel Track Cracking	Edge	LPV 3	Wearing Course	SCRIM	LPV3	Patch
		Settlement		LPV 10	Surface Deterioration		LPV10	
		Rutting						
		Wearing Course						
Sheffield where everyone matters								City Council



Footway Condition Index

- Condition surveys carried out using the UKPMS Footway Network Survey (FNS)
- FCI calculated using a similar approach to the CCI but with the defect types being Structurally, Functionally and Aesthetically Impaired







Process to Date (5)

- May 2009 Potential Bidders submitted PQQs which were then evaluated
- July 2009 Shortlisted three Bidders:
 - Amey bidding as a single organisation, supported by Amey Local Government Limited
 - Carillion lead organisation, forming a consortium with Mouchel Ltd
 - Colas lead organisation, forming a consortium with Scott Wilson, Colas SA and Bank of Scotland





Process to Date (6)

- Dispensed with Invitation to Submit Outline Solution (ISOS) Stage and moved straight into Invitation to Submit Detailed Solution (ISDS) Stage
- Commenced dialogue meetings in September 2009
 - Fortnightly, 1 full day per Bidder
 - 10 rounds of meetings held





Summary of Indicative Project Timetable

Commence Dialogue Process Detailed Solutions Submitted Approval of Shortlisted Bidders Refined Solutions Submitted Final Tenders Submitted Preferred Bidder Appointed Commercial Close Financial Close Contract Starts July 2009 February 2010 June 2010 September 2010 February 2011 March 2011 June2011 July 2011 August 2011





Lessons Learned (1)

- Project Director key appointment
- Experienced, full-time in-house Project Team
- Experienced external advisors
- Level of in-house technical resource required
- Data difficulties





Lessons Learned (2)

- Financial resources required
- Additional costs relating to accrued items
- Clear Objectives
- Early decision on scope and keep it simple
- Broad based Political support







Contact Details

For further details and information about the **Project contact**:

Laurence Alexander Communication & Consultation Officer

Tel: Email: 0114 273 6736 laurence.alexander@sheffield.gov.uk

